

RFB TO-22-11  
4-Leg Parallelogram Lift System  
Questions and Answers #1  
May 13, 2022

- Q1. Can you provide a picture or model of your existing lift to be removed?
- A1. Yes, See Pages 2-4.
- Q2. Surface mount or flush mount installation?
- A2. Surface mount installation.
- Q3. Drive on, back off, or drive through (ramps on both ends of the runaways)?
- A3. Drive on.
- Q4. What is the length of the runways, not including approach ramps?
- A4. 28 feet.
- Q5. What is the longest wheel base of existing fleet or expected (future) wheel base?
- A5. 35 feet is the longest bus we have or intend to purchase.
- Q6. Do you require full runway built in lighting?
- A6. Yes, lighting must be included.
- Q7. Do you require full runway built in air kit?
- A7. Yes, air kit must be included.
- Q8. Do you have underground piping for your control box, an air-line and electrical?
- A8. We have underground piping for our control box, an air-line, and current underground conduit is already installed.
- Q9. Who is responsible for the final electrical hook up to the building?
- A9. The contractor.
- Q10. If we need to do final electrical hook up to the building, who do you use for electrical work?
- A10. Holloway Electric.







